



200 W. Allegan Street, Suite 330 Plainwell , Michigan 49080

Telephone: (269) 685-5181

www.CRAworld.com

Fax: (269) 685-5223

1 dx: (200) 000 0

912265

MEMORANDUM

To:

Sheila Desai, U.S. EPA

REF. NO.:

056394-05-0007

FROM:

Greg Carli/Jeni Quigley/ejh/14/Pwl.

DATE:

November 16, 2012

CC:

Paul Bucholtz, MDEQ Jeffrey Lifka, SulTRAC Richard Gay, Weyerhaeuser

RE:

Revised Summary of Additional Remedial Investigation Activities

PCB-Impacted Soil in the Area of MW-16 Former Plainwell, Inc. Mill Property

Plainwell, Michigan

1.0 INTRODUCTION

Conestoga-Rovers & Associates (CRA), on behalf of Weyerhaeuser Company (Weyerhaeuser), conducted additional Remedial Investigation (RI) activities on the northeastern portion of the Site, in the vicinity of monitoring well MW-16, at the former Plainwell, Inc. Mill Property located at 200 Allegan Street in Plainwell, Michigan (Site). Figure 1 presents the Site layout.

On April 20, 2012, Weyerhaeuser submitted a revised RI Report for the Site in accordance with the RI/Feasibility Study (FS) Work Plan dated July 2009, the Phase II RI Work Plan dated November 20, 2009, the Statement of Work (SOW) for the RI/FS, and the terms of the consent decree for the Design and Implementation of Certain Response Actions at Operable Unit No. 4 and the Plainwell, Inc. Mill Property Operable Unit No. 7 of the Allied Paper, Inc./Portage Creek/Kalamazoo River Superfund Site (Consent Decree), which became effective February 22, 2005. The revised RI Report provided recommendations for additional activities to be completed at the Site to address potential data gaps including the delineation of polychlorinated biphenyl (PCB) impacts identified in soil in the vicinity of MW-16 during the RI.

The additional RI activities summarized in this memorandum were conducted on the northeastern portion of the Site in redevelopment area Commercial Area 4, in the vicinity of monitoring well MW-16, in accordance with the *Work Plan for Additional Remedial Investigation Activities* (Work Plan), submitted to the United States Environmental Protection Agency (U.S. EPA) on May 7, 2012. Approval to initiate this portion of the activities included in the Work Plan was provided by U.S. EPA via email on March 28, 2012.

2.0 SCOPE OF WORK

The Scope of Work (SOW) for the additional investigation in the vicinity of MW-16 included the advancement of soil borings and the collection and analysis of soil samples. Additionally, during the implementation of the additional investigation, MW-16 was modified from a stick-up well to a flush mount well, to accommodate the on-going redevelopment activities at the Site. The investigation field work adhered to the methods and procedures specified in the Phase II RI Work Plan dated November 20, 2009, as approved by the U.S. EPA on January 19, 2010. Additionally, the SOW included the laboratory analysis of

soil samples consistent with the protocols set forth in the Multi-Area Quality Assurance Project Plan (QAPP) dated May 13, 2010 and the Multi-Area Field Sampling Plan (FSP) dated November 20, 2009, submitted to the U.S. EPA under separate cover.

2.1 SOIL BORING INSTALLATION

Nine soil borings (SB-2016 through SB-2024), including one adjacent to MW-16, and at a maximum of 10 feet to the north, south, east, and west of MW-16, were advanced utilizing Geoprobe™ direct push technology with continuous macrocore sampling. One of the soil borings (SB-2020) was advanced adjacent to MW-16 to evaluate additional soil intervals in this location beyond those collected during the RI. The remainder of the initial soil borings was advanced on an approximate 10-foot grid to the north, northeast, northwest, east, west, south, southeast, and southwest of MW-16/SB-2020. An additional six soil borings (SB-2025 through SB-2030) were advanced 10 feet to the north and south of the initial borings. Figure 2 presents the soil boring locations. Soil borings were advanced to 10 feet below ground surface (bgs). Groundwater was encountered between 8 and 10 feet bgs in several of the borings; however, no groundwater samples were collected as part of this investigation. Stratigraphic soil boring logs are presented in Attachment A.

Soil samples were collected continuously at 2-foot intervals, logged, examined by a CRA field technician for visual/olfactory evidence of impact, and screened with a photoionization detector (PID), in accordance with the Phase II RI Work Plan.

Upon completion of soil sample collection, the soil borings were abandoned by backfilling the soil boring annulus with bentonite chips to the ground surface and properly hydrating.

A detailed description of the field methods and procedures utilized was provided in the Phase II RI Work Plan.

2.2 SAMPLING PROCEDURES

All sampling was performed in accordance with the procedures outlined below and in a manner consistent with the QAPP and the FSP. Analytical protocols and parameters are presented in Section 3.0. Table 1 presents a Sample Collection and Analysis Summary.

2.2.1 SOIL SAMPLE COLLECTION

A total of 73 soil samples, including Quality Assurance/Quality Control (QA/QC) samples, were collected during the investigation. Soil samples were collected to represent each 2-foot interval (0 to 2 feet, 2 to 4 feet, 4 to 6 feet, 6 to 8 feet, and 8 to 10 feet) from the ground surface to total depth of the borings, with the exception of SB-2020. Samples were collected from the 4- to 6-foot, 6- to 8-foot, and 8- to 10-foot intervals only from SB-2020.

Soil samples were placed into pre-cleaned laboratory provided containers, labeled, and submitted to the laboratory under chain-of-custody (COC) protocol. A detailed description of the field methods and procedures utilized is provided in the Phase II RI Work Plan.

2.3 DECONTAMINATION

Upon mobilization to the Site and prior to drilling commencement, the drill rig and all associated equipment were thoroughly cleaned using a high-pressure, low-volume steam wash and inspected. The drill rig and other associated equipment were also decontaminated between boring locations to prevent cross-contamination.

All non-disposable sampling equipment were decontaminated prior to each use by using an Alconox wash, potable water rinse, followed by a deionized water rinse and allowed to air dry.

All generated decontamination water was visually examined and screened with a PID. Decontamination water was containerized in a Department of Transportation (DOT) -approved 55-gallon drum for future characterization and disposal.

2.4 MW-16 MODIFICATION

In support of the on-going redevelopment activities in this area of the Site, MW-16 was converted from a stick-up construction well to a flush mount construction well.

The exterior protective casing was removed and the polyvinyl chloride (PVC) pipe was cut to depth. Subsequent to modification, the top of riser was surveyed, consistent with the protocols in the Phase II RI Work Plan.

Removed well construction materials were containerized, along with personnel protection equipment (PPE) (i.e., gloves, etc.) in a DOT-approved 55-gallon drum for future characterization and disposal.

2.5 MANAGEMENT OF INVESTIGATION-DERIVED WASTE (IDW)

IDW generated during the implementation of this investigation was managed and characterized, consistent with the protocols set forth in the Multi-Area FSP. The IDW generated during this investigation will be properly disposed off Site upon receipt and review of waste characterization data.

3.0 ANALYTICAL PROTOCOLS

Soils samples collected from the 0- to 2-foot, 2- to 4-foot, 4- to 6-foot, 6- to 8-foot, and 8- to 10-foot intervals from the borings north, south, east, and west of MW-16 (SB-2016 to SB-2019 and SB-2021 to SB-2024) were submitted for laboratory analysis of PCBs on an accelerated 1-week turnaround time (TAT). Soil samples collected from the 6- to 8-foot and 8- to 10-foot intervals from these borings were submitted to the laboratory on hold, pending the results of the upper intervals. The soil samples collected from the 4- to 6-foot and 6- to 8-foot intervals from the boring adjacent to MW-16 (SB-2020) were also submitted for laboratory analysis of PCBs on an accelerated 1-week TAT. The sample collected from the 8- to 10-foot interval was submitted to the laboratory on hold, pending the results for the upper intervals. All of the soil samples collected from borings SB-2025 through SB-3030 were submitted to the laboratory on hold, pending the results of the samples collected from the initial borings. The samples placed on hold were subsequently analyzed for PCBs on a standard 2-week TAT.

All samples, including QA/QC samples, were collected and analyzed according to the protocols set forth in the Phase II RI Work Plan and QAPP.

4.0 ANALYTICAL DATA EVALUATION

Upon receipt of final analytical data, the data was subjected to the data validation procedures set forth in the QAPP. A copy of the data validation memorandum is presented as Attachment B to this memorandum.

Analytical results for the soil samples collected during the additional RI activities were evaluated against the Generic Cleanup Criteria and Screening Levels established in Part 7 of Administrative Rules, effective March 25, 2011, pursuant to Part 201, Environmental Remediation, 1994 PA 451 as amended (Part 201 Cleanup Criteria). Table 2 presents a summary of analytical results for soil samples collected during this investigation and for samples collected during the RI from MW-16 compared to the Part 201 Cleanup Criteria. A copy of the analytical results is presented in Attachment C to this memorandum.

5.0 ANALYTICAL RESULTS

PCBs were detected above the laboratory method detection limit but below Part 201 Residential Cleanup Criteria in the soil samples collected from 0- to 2-foot interval in a majority of the borings, with the exception of the samples collected from the 0- to 2-foot interval in SB-2018 and SB-2027, where PCBs were not detected.

PCBs were detected in all of the samples collected from the 2- to 4-foot interval in the borings. PCBs detected in the samples collected from the 2- to 4-foot interval at SB-2017, SB-2022, SB-2023, and SB-2030 exceeded the Part 201 Residential Direct Contact Criterion (DCC) of 4 milligrams per kilogram (mg/kg), but were below the Part 201 Non-Residential DCC of 16 mg/kg.

PCBs were detected in all of the samples collected from the 4- to 6-foot interval in the borings. PCBs detected in the samples collected from the 4- to 6-foot interval at SB-2016, SB-2017, SB-2020, SB-2021, and SB-2028 exceeded the Part 201 Non-Residential DCC of 16 mg/kg. PCBs detected in the soil sample collected from SB-2029 exceeded the Part 201 Residential DCC of 4 mg/kg.

PCBs were detected above the Part 201 Non-Residential DCC of 16 mg/kg in the soil samples collected from the 6- to 8-foot interval at SB-2016, SB-2017, SB-2022, and SB-2028 and above the Part 201 Residential DCC of 4 mg/kg in the samples collected from the same interval at SB-2027 and SB-2030. PCBs were detected above laboratory method detection limits, but below Part 201 Residential DCC of 4 mg/kg in the sample collected from the 6 to 8-foot interval at SB-2020. No PCBs were detected in the samples collected from the 6- to 8-foot interval in the remaining borings.

PCBs were detected at or above the Part 201 Non-Residential DCC of 16 mg/kg in the samples collected from 8- to 10-foot interval at SB-2022 and SB-2028 and above the Part 201 Residential DCC of 4 mg/kg in the sample collected from the 8- to 10-foot interval in SB-2030. PCBs were detected above laboratory method detection limits, but below Part 201 Residential Cleanup Criteria in the samples collected from the 8- to 10-foot interval at SB-2016, SB-2017, SB-2020, SB-2022, and SB-2027. No PCBs were detected in the samples collected from the 8- to 10-foot interval in the remaining borings. It should be noted that some of

the soil samples collected from the 8- to 10-foot interval were saturated and are not directly comparable to soil criteria; however, identify whether or not PCBs are present within this interval.

Total PCBs detected in the soil samples consisted of one or more of the following Aroclors: Aroclor-1242, Aroclor-1248 and Aroclor-1254. Figures 3A through 3E illustrate the distribution and concentrations of total PCBs detected in soil for the 0- to 2-foot, 2- to 4-foot, 4- to 6-foot, 6- to 8-foot, and 8- to 10-foot intervals, respectively.

Field observations made during the soil boring installation activities were noted on the soil boring logs as identified in Section 2.1. The following observations were made pertaining to potential visual impacts observed in the soil borings:

- SB-2026 Possible coal fragments at 2.5 feet bgs
- SB-2019 Coal fragments, wood debris at 4.5 feet bgs
- SB-2024 Coal fragments, slag, black cinders, and brick fragments between 4.8 and 6.0 feet bgs
- SB-2018 Slag, black cinders, brick debris from 3.0 to 4.0 feet bgs
- SB-2025 Slag, coal pieces, brick fragments, cinders from 3.5 to 5.0 feet bgs
- SB-2021 Black at 7.5 feet bgs
- SB-2020 Black at 4.8 feet and 7.5 feet bgs
- SB-2023 Slag, brick, debris at 5.5 feet bgs, black clay at 6.0 feet bgs
- SB-2029 Dark brown to black organics at 3.7 feet, cinders and slag from 7.5 to 7.7 feet bgs
- SB-2028 Black with organics at 8.0 feet bgs
- SB-2016 Possible coal at 2.5 feet bgs
- SB-2030 Slag from 5.0 to 5.5 feet bgs

A review of the detected PCB concentrations in soil compared to the above field observations for potential impacts noted in the soil borings does not show a correlation (e.g., typically observations of impact had low PCB concentrations). However, a gray clay material was observed in a number of the soil borings, which often corresponded to elevated PCB concentrations.

6.0 CONCLUSIONS

PCBs are present in soil in the northeastern portion of the Site above Part 201 Residential and Non-Residential DCC.

During the RI, PCBs were detected above Part 201 Residential DCC in the soil sample collected from the 0- to 2-foot interval in MW-16. Based on laboratory analytical results for soil samples collected during this investigation, the greatest impacts were observed in soil borings located near the top of the bank of the Mill Race Drain, to the north and east of MW-16. In these locations, soil samples collected closer to the water table (i.e., 4 to 10 feet bgs) had higher concentrations of PCBs than the samples collected from shallower


depths (i.e., <4 feet bgs). No PCBs were detected above Part 201 Cleanup Criteria in any of the soil samples collected immediately adjacent to the former Mill Building.


Based on the pattern of PCBs observed in the soil borings, one possibility is that the source of the elevated PCBs observed in the investigation area is the adjacent Mill Race. During preparation of the RI Report, CRA reviewed historical records and did not identify any Site-related pipes, tanks, electrical equipment or other operations in this area that could potentially be the source of the PCB impacts. Therefore, given that the highest concentrations of PCB-impacted material are located toward the Mill Race, which is known to contain PCB impacted sediments similar in nature to the PCBs observed in this area, the highest impacts are at depth (i.e., not consistent with a surface release), and there does not appear to be a source of PCBs in this vicinity of the Site related to historical Site operations, it is presumed that the source of the PCBs in this area is the Mill Race. Based on this premise, it is anticipated that PCB-impacted material is present to some degree between the row of soil borings located along the top of the riverbank toward the Mill Race. Given the logistical challenges with installing additional soil boring toward the Mill Race (i.e., steep slope and close proximity to the water), further investigation of this material is not proposed, but instead it is anticipated this area will be addressed through remedial activities.


It is also noted that PCB impacts may be present to the south of soil boring SB-2030; however, the impacts observed in this soil boring are below the Michigan Act 451, Part 201 soil criteria for Non-Residential use, which is the appropriate standard for this portion of the Site (i.e., commercial use). Therefore, unless the land use in this area changes, there is no need to further delineate the extent of PCB impacts further to the south.


Elevated PCB concentrations were present in several locations at or near the water table. The SOW for this investigation did not include the collection and analysis of groundwater samples for PCBs; therefore, no determination can be made on whether or not groundwater in the vicinity of the investigation area is impacted by PCBs. Further evaluation of the potential for PCB impacted groundwater to be present in this area may be required at a future time, depending on the remedial approach for this area.


.

















TABLES

TABLE 1

Page 1 of 2

SAMPLE COLLECTION AND ANALYSIS SUMMARY ADDITIONAL REMEDIAL INVESTIGATION ACTIVITIES PCB-IMPACTED SOIL AT MW-16 FORMER PLAINWELL, INC. MILL PROPERTY PLAINWELL, MICHIGAN

Sample Identification	Sample Location	Sample Depth	<u>Matrix</u>	QC Sample	<u>Analysis</u>
SO-56394-032912-EB-001	SB-2020	4 - 6 ft bgs	Soil		PCBs
SO-56394-032912-EB-002	SB-2020	6 - 8 ft bgs	Soil		PCBs
SO-56394-032912-EB-003	SB-2020	8 - 10 ft bgs	Soil		PCBs
SO-56394-032912-EB-004	SB-2021	0 - 2 ft bgs	Soil		PCBs
SO-56394-032912-EB-004A	SB-2021	0 - 2 ft bgs	Soil	Duplicate (-004)	PCBs
SO-56394-032912-EB-005	SB-2021	2 - 4 ft bgs	Soil	• , ,	PCBs
SO-56394-032912-EB-006	SB-2021	4 - 6 ft bgs	Soil		PCBs
SO-56394-032912-EB-007	SB-2021	6 - 8 ft bgs	Soil		PCBs
SO-56394-032912-EB-008	SB-2021	8 - 10 ft bgs	Soil		PCBs
SO-56394-032912-EB-009	SB-2016	0 - 2 ft bgs	Soil		PCBs
SO-56394-032912-EB-010	SB-2016	2 - 4 ft bgs	Soil		PCBs
SO-56394-032912-EB-011	SB-2016	4 - 6 ft bgs	Soil .		PCBs
SO-56394-032912-EB-012	SB-2016	6 - 8 ft bgs	Soil		PCBs
SO-56394-032912-EB-013	SB-2016	8 - 10 ft bgs	Soil		PCBs
SO-56394-032912-EB-014	SB-2019	0 - 2 ft bgs	Soil		PCBs
SO-56394-032912-EB-015	SB-2019	2 - 4 ft bgs	Soil		PCBs
SO-56394-032912-EB-016	SB-2019	4 - 6 ft bgs	Soil	MS/MSD	PCBs
SO-56394-032912-EB-017	SB-2019	6 - 8 ft bgs	Soil		PCBs
SO-56394-032912-EB-018	SB-2019	8 - 10 ft bgs	Soil		PCBs
SO-56394-032912-EB-019	SB-2024	0 - 2 ft bgs	Soil	T 11 (010)	PCBs
SO-56394-032912-EB-019A	SB-2024	0 - 2 ft bgs	Soil	Duplicate (-019)	PCBs
SO-56394-032912-EB-020	SB-2024	2 - 4 ft bgs	Soil		PCBs
SO-56394-032912-EB-021	SB-2024	4 - 6 ft bgs	Soil		PCBs
SO-56394-032912-EB-022	SB-2024	6 - 8 ft bgs	Soil		PCBs
SO-56394-032912-EB-023	SB-2024	8 - 10 ft bgs	Soil		PCBs
SO-56394-032912-EB-024	SB-2018	0 - 2 ft bgs	Soil		PCBs
SO-56394-032912-EB-025	SB-2018	2 - 4 ft bgs	Soil		PCBs
SO-56394-032912-EB-026	SB-2018 SB-2018	4 - 6 ft bgs 6 - 8 ft bgs	Soil Soil		PCBs PCBs
SO-56394-032912-EB-027 SO-56394-032912-EB-028	SB-2018	8 - 10 ft bgs	Soil		PCBs
SO-56394-032912-EB-029	SB-2023	0 - 10 ft bgs	Soil		PCBs
SO-56394-032912-EB-029A	SB-2023	0 - 2 ft bgs	Soil	Duplicate (-029)	PCBs
SO-56394-032912-EB-030	SB-2023	2 - 4 ft bgs	Soil	Duplicate (-02)	PCBs
SO-56394-032912-EB-030A	SB-2023	2 - 4 ft bgs	Soil	Duplicate (-030)	PCBs
SO-56394-032912-EB-031	SB-2023	4 - 6 ft bgs	Soil	z upitetto (coo)	PCBs
SO-56394-032912-EB-032	SB-2023	6 - 8 ft bgs	Soil		PCBs
SO-56394-032912-EB-033	SB-2023	8 - 10 ft bgs	Soil		PCBs
SO-56394-032912-EB-034	SB-2017	0 - 2 ft bgs	Soil		PCBs
SO-56394-032912-EB-035	SB-2017	2 - 4 ft bgs	Soil		PCBs
SO-56394-032912-EB-036	SB-2017	4 - 6 ft bgs	Soil		PCBs
SO-56394-032912-EB-037	SB-2017	6 - 8 ft bgs	Soil		PCBs
SO-56394-032912-EB-037A	SB-2017	6 - 8 ft bgs	Soil	Duplicate (-037)	PCBs
SO-56394-032912-EB-038	SB-2017	8 - 10 ft bgs	Soil		PCBs
SO-56394-032912-EB-038A	SB-2017	8 - 10 ft bgs	Soil	Duplicate (-038)	PCBs
SO-56394-032912-EB-039	SB-2022	0 - 2 ft bgs	Soil	MS/MSD	PCBs
SO-56394-032912-EB-040	SB-2022	2 - 4 ft bgs	Soil		PCBs
SO-56394-032912-EB-041	SB-2022	4 - 6 ft bgs	Soil		PCBs
SO-56394-032912-EB-042	SB-2022	6 - 8 ft bgs	Soil		PCBs
SO-56394-032912-EB-043	SB-2022	8 - 10 ft bgs	Soil		PCBs
SO-56394-032912-EB-043A	SB-2022	8 - 10 ft bgs	Soil	Duplicate (-043)	PCBs
SO-56394-032912-EB-044	SB-2026	0 - 2 ft bgs	Soil	MS/MSD	PCBs
SO-56394-032912-EB-045	SB-2026	2 - 4 ft bgs	Soil	D 1: ((045)	PCBs
SO-56394-032912-EB-045A	SB-2026	2 - 4 ft bgs	Soil	Duplicate (-045)	PCBs
SO-56394-032912-EB-046	SB-2026	4 - 6 ft bgs	Soil		PCBs
SO-56394-032912-EB-047	SB-2026	6 - 8 ft bgs	Soil		PCBs
SO-56394-032912-EB-048	SB-2026	8 - 10 ft bgs	Soil		PCBs
SO-56394-032912-EB-049	SB-2027	0 - 2 ft bgs	Soil	MC /MCD	PCBs
SO-56394-032912-EB-050	SB-2027	2 - 4 ft bgs	Soil	MS/MSD	PCBs
SO-56394-032912-EB-051 SO-56394-032912-EB-052	SB-2027 SB 2027	4 - 6 ft bgs	Soil		PCBs
SO-56394-032912-EB-052A	SB-2027 SB-2027	6 - 8 ft bgs 6 - 8 ft bgs	Soil Soil	Dunlicate (052)	PCBs PCBs
30-3037 1- 032712-ED-032A	30-202/	o - o it bgs	5011	Duplicate (-052)	PCDS

TABLE 1

SAMPLE COLLECTION AND ANALYSIS SUMMARY ADDITIONAL REMEDIAL INVESTIGATION ACTIVITIES PCB-IMPACTED SOIL AT MW-16 FORMER PLAINWELL, INC. MILL PROPERTY PLAINWELL, MICHIGAN

Sample Identification	Sample Location	Sample Depth	<u>Matrix</u>	QC Sample	<u>Analysis</u>
SO-56394-032912-EB-001	SB-2020	4 - 6 ft bgs	Soil		PCBs
SO-56394-032912-EB-002	SB-2020	6 - 8 ft bgs	Soil	•	PCBs
SO-56394-032912-EB-003	SB-2020	8 - 10 ft bgs	Soil		PCBs
SO-56394-032912-EB-004	SB-2021	0 - 2 ft bgs	Soil		PCBs
SO-56394-032912-EB-004A	SB-2021	0 - 2 ft bgs	Soil	Duplicate (-004)	PCBs
SO-56394-032912-EB-005	SB-2021	2 - 4 ft bgs	Soil		PCBs
SO-56394-032912-EB-053	SB-2027	8 - 10 ft bgs	Soil		PCBs
SO-56394-032912-EB-054	SB-2028	0 - 2 ft bgs	Soil		PCBs
SO-56394-032912-EB-055	SB-2028	2 - 4 ft bgs	Soil		PCBs
SO-56394-032912-EB-056	SB-2028	4 - 6 ft bgs	Soil		PCBs
SO-56394-032912-EB-057	SB-2028	6 - 8 ft bgs	Soil		PCBs
SO-56394-032912-EB-058	SB-2028	8 - 10 ft bgs	Soil		PCBs
SO-56394-032912-EB-059	SB-2025	0 - 2 ft bgs	Soil		PCBs
SO-56394-032912-EB-060	SB-2025	2 - 4 ft bgs	Soil		PCBs
SO-56394-032912-EB-061	SB-2025	4 - 6 ft bgs	Soil		PCBs
SO-56394-032912-EB-062	SB-2025	6 - 8 ft bgs	Soil		PCBs
SO-56394-032912-EB-063	SB-2025	8 - 10 ft bgs	Soil		PCBs
SO-56394-032912-EB-064	SB-2029	0 - 2 ft bgs	Soil		PCBs
SO-56394-032912-EB-065	SB-2029	2 - 4 ft bgs	Soil		PCBs
SO-56394-032912-EB-066	SB-2029	4 - 6 ft bgs	Soil		PCBs
SO-56394-032912-EB-067	SB-2029	6 - 8 ft bgs	Soil		PCBs
SO-56394-032912-EB-068	SB-2029	8 - 10 ft bgs	Soil		PCBs
SO-56394-032912-EB-069	SB-2030	0 - 2 ft bgs	Soil		PCBs
SO-56394-032912-EB-070	SB-2030	2 - 4 ft bgs	Soil		PCBs
SO-56394-032912-EB-071	SB-2030	4 - 6 ft bgs	Soil		PCBs
SO-56394-032912-EB-072	SB-2030	6 - 8 ft bgs	Soil		PCBs
SO-56394-032912-EB-073	SB-2030	8 - 10 ft bgs	Soil		PCBs

Notes:

PCBs - Polychlorinated Biphenyls QC - Quality Control ft bgs - feet below ground surface MS/MSD - Matrix Spike / Matrix Spike Duplicate

TABLE 2 Page 1 of 11

SUMMARY OF ANALYTICAL RESULTS ADDITIONAL REMEDIAL INVESTIGATION ACTIVITIES PCB-IMPACTED SOIL AT MW-16 FORMER PLAINWELL, INC. MILL PROPERTY PLAINWELL, MICHIGAN

		Michigan Act	451, Part 201 Clea	nup Criteria and Part	213 Risk-based	Screening Levels: Resi	idential and Non-Resid	ential Generic C	leanup Criteria ⁽¹⁾
		Residential	Non-Residential	Groundwater	Groundwater	Residential Soil	Non-Residential Soil	Residential	Non-Residential
		Drinking Water	Drinking Water	Surface Water	Contact	Volatilization to	Volatilization to	Infinite Source	Infinite Source
		Protection	Protection	Interface Protection	Protection	Indoor Air Inhalation	Indoor Air Inhalation	Volatile Soil	Volatile Soil
		ь	c	d	e	f	g	h	i
	Units								
Polychlorinated Biphenyls (PCBs)									
Aroclor-1016 (PCB-1016)	mg/kg	NC	NC	NC	NC	NC	NC	NC	NC
Aroclor-1221 (PCB-1221)	mg/kg	NC	NC	NC	NC	NC	NC	NC	NC
Aroclor-1232 (PCB-1232)	mg/kg	NC	NC	NC	NC	NC	NC	NC	NC
Aroclor-1242 (PCB-1242)	mg/kg	NC	NC	NC	NC	NC	NC	NC	NC
Aroclor-1248 (PCB-1248)	mg/kg	NC	NC	NC	NC	NC	NC	NC	NC
Aroclor-1254 (PCB-1254)	mg/kg	NC	NC	NC	NC	NC	NC	NC	NC
Aroclor-1260 (PCB-1260)	mg/kg	NC	NC	NC	NC	NC	NC	NC	NC
Total PCBs	mg/kg	NLL	NLL	NLL	NLL	3000	16000	240	810

Notes:

(1) Cleanup criteria identified by MDEQ RRD Op

Memo No. 1, updated 3/25/2011, pursuant to

1994 PA 451 as amended

ft BGS - feet below ground surface

U - Not present at or above the associated value

J - Estimated concentration

UJ - Estimated reporting limit

NLL - Not likely to leach

NC - No criteria

TABLE 2 Page 2 of 11

SUMMARY OF ANALYTICAL RESULTS ADDITIONAL REMEDIAL INVESTIGATION ACTIVITIES PCB-IMPACTED SOIL AT MW-16 FORMER PLAINWELL, INC. MILL PROPERTY PLAINWELL, MICHIGAN

		Michigan Act 45	51, Part 201 Cleanup	Criteria and Part 2	13 Risk-based Screer	ning Levels: Residen	tial and Non-Resider	ntial Generic Cl	eanup Criteria ⁽¹⁾
		Residential	Non-Residential	Residential	Non-Residential	Residential	Non-Residential	Residential	Non-Residential
		Finite VSIC for	Finite VSIC for	Finite VSIC for	Finite VSIC for	Particulate	Particulate	Direct	Direct
		5 Meter Source	5 Meter Source	2 Meter Source	2 Meter Source	Soil Inhalation	Soil Inhalation	Contact	Contact
		j	k	1	m	n	o	P	q
	Units								
Polychlorinated Biphenyls (PCBs)									
Aroclor-1016 (PCB-1016)	mg/kg	NC	NC	NC	NC	NC	NC	NC	NC
Aroclor-1221 (PCB-1221)	mg/kg	NC	NC	NC	NC	NC	NC	NC	NC
Aroclor-1232 (PCB-1232)	mg/kg	NC	NC	NC	NC	NC	NC	NC	NC
Aroclor-1242 (PCB-1242)	mg/kg	NC	NC	NC	NC	NC	NC	NC	NC
Aroclor-1248 (PCB-1248)	mg/kg	NC	NC	NC	NC	NC	NC	NC	NC
Aroclor-1254 (PCB-1254)	mg/kg	NC	NC	NC	NC	NC	NC	NC	NC
Aroclor-1260 (PCB-1260)	mg/kg	NC	NC	NC	NC	NC	NC	NC	NC
Total PCBs	mg/kg	7900	28000	7900	28000	5200	6500	4	16

Notes:

(1) Cleanup criteria identified by MDEQ RRD Op Memo No. 1, updated 3/25/2011, pursuant to 1994 PA 451 as amended ft BGS - feet below ground surface U - Not present at or above the associated value J - Estimated concentration UJ - Estimated reporting limit

NLL - Not likely to leach NC - No criteria TABLE 2 Page 3 of 11

Sample Location Sample Identification (SO-56) Sample Date Sample Depth Sample Type	394-) Units	SB-2016 032912-EB-009 3/29/2012 (0-2) ft BGS	SB-2016 032912-EB-010 3/29/2012 (2-4) ft BGS	SB-2016 032912-EB-011 3/29/2012 (4-6) ft BGS	SB-2016 032912-EB-012 3/29/2012 (6-8) ft BGS	SB-2016 032912-EB-013 3/29/2012 (8-10) ft BGS	SB-2017 032912-EB-034 3/29/2012 (0-2) ft BGS	SB-2017 032912-EB-035 3/29/2012 (2-4) ft BGS	SB-2017 032912-EB-036 3/29/2012 (4-6) ft BGS	SB-2017 032912-EB-037 3/29/2012 (6-8) ft BGS	SB-2017 032912-EB-037A 3/29/2012 (6-8) ft BGS Duplicate
Polychlorinated Biphenyls (F	PCBs)										
Aroclor-1016 (PCB-1016)	mg/kg	0.0075 U	0.072 U	0.93 U	1.1 U	0.078 U	0.0067 U	0.79 U	1.1 U	1.1 U	2 U
Aroclor-1221 (PCB-1221)	mg/kg	0.015 U	0.15 U	1.9 U	2.2 U	0.16 U	0.014 U	1.6 U	2.2 U	2.1 U	4 U
Aroclor-1232 (PCB-1232)	mg/kg	0.0075 U	0.072 U	0.93 U	1.1 U	0.078 U	0.0067 U	0.79 U	1.1 U	1.1 U	2 U
Aroclor-1242 (PCB-1242)	mg/kg	0.0075 U	0.072 U	0.93 U	53	2.4	0.0067 U	0.79 U	1.1 U	35	29
Aroclor-1248 (PCB-1248)	mg/kg	0.33	1.6	17	1.1 U	0.078 U	0.0067 U	8.3	28	1.1 U	2 U
Aroclor-1254 (PCB-1254)	mg/kg	0.0075 U	0.072 U	0.93 U	1.1 U	0.078 U	0.0028 J	6.2	1.1 U	1.1 U	2 U
Aroclor-1260 (PCB-1260)	mg/kg	0.0075 U	0.072 U	0.93 U	1.1 U	0.078 U	0.0067 U	0.79 U	1.1 U	1.1 U	2 U
Total PCBs	mg/kg	0.33	1.6	17 ^{pq}	53 ^{pq}	2.4	0.0028 J	14.5 ^p	28 ^{pq}	35 ^{pq}	29 ^{pq}

Sample Location Sample Identification (SO-56 Sample Date Sample Depth Sample Type	394-) Units	SB-2017 032912-EB-038 3/29/2012 (8-10) ft BGS	SB-2017 032912-EB-038A 3/29/2012 (8-10) ft BGS Duplicate	SB-2018 032912-EB-024 3/29/2012 (0-2) ft BGS	SB-2018 032912-EB-025 3/29/2012 (2-4) ft BGS	SB-2018 032912-EB-026 3/29/2012 (4-6) ft BGS	SB-2018 032912-EB-027 3/29/2012 (6-8) ft BGS	SB-2018 032912-EB-028 3/29/2012 (8-10) ft BGS	SB-2019 032912-EB-014 3/29/2012 (0-2) ft BGS	SB-2019 032912-EB-015 3/29/2012 (2-4) ft BGS	SB-2019 032912-EB-016 3/29/2012 (4-6) ft BGS
Polychlorinated Biphenyls (I	PCBs)										
Aroclor-1016 (PCB-1016)	mg/kg	0.066 U	0.0084 U	0.0065 U	0.0071 U	0.0072 U	0.0055 U	0.0054 U	0.0071 U	0.0072 U	0.0072 U
Aroclor-1221 (PCB-1221)	mg/kg	0.14 U	0.017 U	0.013 U	0.015 U	0.015 U	0.011 U	0.011 U	0.015 U	0.015 U	0.015 U
Aroclor-1232 (PCB-1232)	mg/kg	0.066 U	0.0084 U	0.0065 U	0.0071 U	0.0072 U	0.0055 U	0.0054 U	0.0071 U	0.0072 U	0.0072 U
Aroclor-1242 (PCB-1242)	mg/kg	0.027 J	0.063 J	0.0065 U	0.0071 U	0.0072 U	0.0055 U	0.0054 U	0.0071 U	0.0072 U	0.0072 U
Aroclor-1248 (PCB-1248)	mg/kg	0.066 U	0.0084 U	0.0065 U	0.0071 U	0.0072 U	0.0055 U	0.0054 U	0.0071 U	0.0072 U	0.0072 U
Aroclor-1254 (PCB-1254)	mg/kg	0.024 J	0.0084 U	0.0065 U	0.12	0.0058 J	0.0055 U	0.0054 U	0.033	0.035	0.0022 J
Aroclor-1260 (PCB-1260)	mg/kg	0.066 U	0.0084 U	0.0065 U	0.0071 U	0.0054 J	0.0055 U	0.0054 U	0.0071 U	0.0072 U	0.0072 U
Total PCBs	mg/kg	0.051 J	0.063 J	ND	0.12	0.0112 J	ND	ND	0.033	0.035	0.0022 J

Sample Location Sample Identification (SO-563 Sample Date Sample Depth Sample Type	994-) Units	SB-2019 032912-EB-017 3/29/2012 (6-8) ft BGS	SB-2019 032912-EB-018 3/29/2012 (8-10) ft BGS	SB-2020 032912-EB-001 3/29/2012 (4-6) ft BGS	SB-2020 032912-EB-002 3/29/2012 (6-8) ft BGS	SB-2020 032912-EB-003 3/29/2012 (8-10) ft BGS	SB-2021 032912-EB-004 3/29/2012 (0-2) ft BGS	SB-2021 032912-EB-004A 3/29/2012 (0-2) ft BGS Duplicate	SB-2021 032912-EB-005 3/29/2012 (2-4) ft BGS	SB-2021 032912-EB-006 3/29/2012 (4-6) ft BGS	SB-2021 032912-EB-007 3/29/2012 (6-8) ft BGS
Polychlorinated Biphenyls (P	CBs)										
Aroclor-1016 (PCB-1016)	mg/kg	0.0058 U	0.0058 U	0.011 U	0.014 U	0.0087 U	0.0069 U	0.0054 U	0.0073 U	0.85 U	0.092 U
Aroclor-1221 (PCB-1221)	mg/kg	0.012 U	0.012 U	0.022 U	0.027 U	0.018 U	0.014 U	0.011 U	0.015 U	1.7 U	0.19 U
Aroclor-1232 (PCB-1232)	mg/kg	0.0058 U	0.0058 U	0.011 U	0.014 U	0.0087 U	0.0069 U	0.0054 U	0.0073 U	0.85 U	0.092 U
Aroclor-1242 (PCB-1242)	mg/kg	0.0058 U	0.0058 U	0.011 U	0.014 U	0.0087 U	0.0069 U	0.0054 U	0.0073 U	0.85 U	0.092 U
Aroclor-1248 (PCB-1248)	mg/kg	0.0058 U	0.0058 U	0.14	0.019	0.0033 J	0.11	0.078	0.35	25	0.092 U
Aroclor-1254 (PCB-1254)	mg/kg	0.0058 U	0.0058 U	0.011 U	0.014 U	0.0087 U	0.0069 UJ	0.072 J	0.0073 U	0.85 U	0.092 U
Aroclor-1260 (PCB-1260)	mg/kg	0.0058 U	0.0058 U	. 0.011 U	0.014 U	0.0087 U	0.0069 U	0.0054 U	0.0073 U	0.85 U	0.092 U
Total PCBs	mg/kg	ND	ND	0.14	0.019	0.0033 J	0.11 J	0.15 J	0.35	25 ^{pq}	ND

TABLE 2 Page 6 of 11

Sample Location Sample Identification (SO-56 Sample Date Sample Depth Sample Type	394-) Units	SB-2021 032912-EB-008 3/29/2012 (8-10) ft BGS	SB-2022 032912-EB-039 3/29/2012 (0-2) ft BGS	SB-2022 032912-EB-040 3/29/2012 (2-4) ft BGS	SB-2022 032912-EB-041 3/29/2012 (4-6) ft BGS	SB-2022 032912-EB-042 3/29/2012 (6-8) ft BGS	SB-2022 032912-EB-043 3/29/2012 (8-10) ft BGS	SB-2022 032912-EB-043A 3/29/2012 (8-10) ft BGS Duplicate	SB-2023 032912-EB-029 3/29/2012 (0-2) ft BGS	SB-2023 032912-EB-029A 3/29/2012 (0-2) ft BGS Duplicate	SB-2023 032912-EB-030 3/29/2012 (2-4) ft BGS
Polychlorinated Biphenyls (I	PCRe)										ì
Aroclor-1016 (PCB-1016)	mg/kg	0.1 U	0.0068 U	0.79 U	1.1 U	1.1 U	0.92 U	0.098 U	0.0072 U	0.014 U	0.78 U
	1,7. 1.										
Aroclor-1221 (PCB-1221)	mg/kg	0.2 U	0.014 U	1.6 U	2.1 U	2.1 U	1.9 U	0.2 U	0.015 U	0.028 U	1.6 U
Aroclor-1232 (PCB-1232)	mg/kg	0.1 U	0.0068 U	0.79 U	1.1 U	1.1 U	0.92 U	0.098 U	0.0072 U	0.014 U	0.78 U
Aroclor-1242 (PCB-1242)	mg/kg	0.1 U	0.0068 U	0.79 U	1.1 U	47	16 J	3.3 J	0.0072 U	0.014 U	0.78 U
Aroclor-1248 (PCB-1248)	mg/kg	0.1 U	0.11	4.7	17	1.1 U	0.92 U	0.098 U	0.27	0.38 J	7.1
Aroclor-1254 (PCB-1254)	mg/kg	0.1 U	0.083	0.79 U	1.1 U	1.1 U	0.92 U	0.098 U	0.0072 U	0.014 U	0.78 U
Aroclor-1260 (PCB-1260)	mg/kg	0.1 U	0.0068 U	0.79 U	1.1 U	1.1 U	0.92.U	0.098 U	0.0072 U	0.014 U	0.78 U
Total PCBs	mg/kg	ND	0.193	4.7°	17 ^{pq}	47 ^{pq}	16 J ^p	3.3 J	0.27	0.38 J	7.1 ^p

TABLE 2 Page 7 of 11

Sample Location Sample Identification (SO-56 Sample Date Sample Depth Sample Type	394-) Units	SB-2023 032912-EB-030A 3/29/2012 (2-4) ft BGS Duplicate	SB-2023 032912-EB-031 3/29/2012 (4-6) ft BGS	SB-2023 032912-EB-032 3/29/2012 (6-8) ft BGS	SB-2023 032912-EB-033 3/29/2012 (8-10) ft BGS	SB-2024 032912-EB-019 3/29/2012 (0-2) ft BGS	5B-2024 032912-EB-019A 3/29/2012 (0-2) ft BGS	SB-2024 032912-EB-020 3/29/2012 (2-4) ft BGS	SB-2024 032912-EB-021 3/29/2012 (4-6) ft BGS	SB-2024 032912-EB-022 3/29/2012 (6-8) ft BGS	SB-2024 032912-EB-023 3/29/2012 (8-10) ft BGS
Polychlorinated Biphenyls (I	PCBs)										
Aroclor-1016 (PCB-1016)	mg/kg	0.059 U	0.11 U	0.093 U	0.093 U	0.0072 U	0.0055 U	0.0069 U	0.0094 U	0.0091 U	0.0059 U
Aroclor-1221 (PCB-1221)	mg/kg	0.12 U	0.21 U	0.19 U	0.19 U	0.015 U	0.011 U	0.014 U	0.019 U	0.019 U	0.012 U
Aroclor-1232 (PCB-1232)	mg/kg	0.059 U	0.11 U	0.093 U	0.093 U	0.0072 U	0.0055 U	0.0069 U	0.0094 U	0.0091 U	0.0059 U
Aroclor-1242 (PCB-1242)	mg/kg	0.059 U	0.11 U	0.093 U	0.093 U	0.0072 U	0.0055 U	0.0069 U	0.0094 U	0.0091 U	0.0059 U
Aroclor-1248 (PCB-1248)	mg/kg	2.7	2.3	0.093 U	0.093 U	0.0072 UJ	0.024 J	0.33	0.0094 U	0.0091 U	0.0059 U
Aroclor-1254 (PCB-1254)	mg/kg	0.059 U	0.11 U	0.093 U	0.093 U	0.034	0.023	0.24	0.0025 J	0.0091 U	0.0059 U
Aroclor-1260 (PCB-1260)	mg/kg	0.059 U	0.11 U	0.093 U	0.093 U	0.0072 U	0.0055 U	0.0069 U	0.0094 U	0.0091 U	0.0059 U
Total PCBs	mg/kg	2.7	2.3	ND	ND	0.034 J	0.047 J	0.57	0.00 2 5 J	ND	ND

TABLE 2 Page 8 of 11

Sample Location Sample Identification (SO-56: Sample Date Sample Depth Sample Type	394-) Units	SB-2025 032912-EB-059 3/29/2012 (0-2) ft BGS	SB-2025 032912-EB-060 3/29/2012 (2-4) ft BGS	SB-2025 032912-EB-061 3/29/2012 (4-6) ft BGS	SB-2025 032912-EB-062 3/29/2012 (6-8) ft BGS	SB-2025 032912-EB-063 3/29/2012 (8-10) ft BGS	SB-2026 032912-EB-044 3/29/2012 (0-2) ft BGS	SB-2026 032912-EB-045 3/29/2012 (2-4) ft BGS	SB-2026 032912-EB-045A 3/29/2012 (2-4) ft BGS Duplicate	SB-2026 032912-EB-046 3/29/2012 (4-6) ft BGS	SB-2026 032912-EB-047 3/29/2012 (6-8) ft BGS
Polychlorinated Biphenyls (I	PCBs)										
Aroclor-1016 (PCB-1016)	mg/kg	0.0055 U	0.0057 U	0.0065 U	0.0054 U	0.0054 U	0.0055 U	0.0056 U	0.014	0.0062 U	0.0055 U
Aroclor-1221 (PCB-1221)	mg/kg	0.011 U	0.012 U	0.013 U	0.011 U	0.011 U	0.011 U	0.012 U	0.012	0.013 U	0.011 U
Aroclor-1232 (PCB-1232)	mg/kg	0.0055 U	0.0057 U	0.0065 U	0.0054 U	0.0054 U	0.0055 U	0.0056 U	0.032	0.0062 U	0.0055 U
Aroclor-1242 (PCB-1242)	mg/kg	0.0055 U	0.0057 U	0.0065 U	0.0054 U	0.0054 U	0.0063	0.0056 U	0.024	0.0062 U	0.0055 U
Aroclor-1248 (PCB-1248)	mg/kg	0.0055 U	0.0057 U	0.0065 U	0.0054 U	0.0054 U	0.0055 U	0.0056 U	0.053	0.0062 U	0.0055 U
Aroclor-1254 (PCB-1254)	mg/kg	0.063	0.032	0.079	0.0054 U	0.0054 U	0.032	0.058	0.065	0.0066	0.0055 U
Aroclor-1260 (PCB-1260)	mg/kg	0.0055 U	0.0057 U	0.0065 U	0.0054 U	0.0054 U	0.0055 U	0.0056 U	0.0056 U	0.0062 U	0.0055 U
Total PCBs	mg/kg	0.063	0.032	0.079	ND	ND	0.032	0.058	0.065	0.0066	ND

Sample Location Sample Identification (SO-56: Sample Date Sample Depth Sample Type	394-) Units	SB-2026 032912-EB-048 3/29/2012 (8-10) ft BGS	SB-2027 032912-EB-049 3/29/2012 (0-2) ft BGS	SB-2027 032912-EB-050 3/29/2012 (2-4) ft BGS	SB-2027 032912-EB-051 -3/29/2012 (4-6) ft BGS	SB-2027 032912-EB-052 3/29/2012 (6-8) ft BGS	SB-2027 032912-EB-052A 3/29/2012 (6-8) ft BGS Duplicate	SB-2027 032912-EB-053 3/29/2012 (8-10) ft BGS	SB-2028 032912-EB-054 3/29/2012 (0-2) ft BGS	SB-2028 032912-EB-055 3/29/2012 (2-4) ft BGS	SB-2028 032912-EB-056 3/29/2012 (4-6) ft BGS
Polychlorinated Biphenyls (I	PCBs)										
Aroclor-1016 (PCB-1016)	mg/kg	0.0057 U	0.018	0.0052 U	0.028 U	0.42 U	0.14 U	0.0058 U	0.0053 U	0.027 U	1.3 U
Aroclor-1221 (PCB-1221)	mg/kg	0.012 U	0.012	0.011 U	0.055 U	0.84 U	0.28 U	0.012 U	0.011 U	0.054 U	2.5 U
Aroclor-1232 (PCB-1232)	mg/kg	0.0057 U	0.024	0.0052 U	0.028 U	0.42 U	0.14 U	0.0058 U	0.0053 U	0.027 U	1.3 U
Aroclor-1242 (PCB-1242)	mg/kg	0.0057 U	0.023	0.0052 U	0.028 U	0.42 U	0.14 U	0.0058 U	0.0053 U	0.027 U	17
Aroclor-1248 (PCB-1248)	mg/kg	0.0057 U	0.021	0.092 J	0.91	7.4	3.4	0.1	0.0053 U	0.45	1.3 U
Aroclor-1254 (PCB-1254)	mg/kg	0.0057 U	0.026	0.0052 U	0.028 U	0.42 U	0.14 U	0.0058 U	0.044	0.027 U	1.3 U
Aroclor-1260 (PCB-1260)	mg/kg	0.0057 U	0.026	0.0052 U	0.028 Ų	0.42 U	0.14 U	0.0058 U	0.0053 U	0.027 U	1.3 U
Total PCBs	mg/kg	ND	ND	0.092 J	0.91	7.4 ^p	3.4	0.1	0.044	0.45	17 ^{pq}

Sample Location Sample Identification (SO-56 Sample Date Sample Depth Sample Type	394-) Units	SB-2028 032912-EB-057 3/29/2012 (6-8) ft BGS	SB-2028 032912-EB-058 3/29/2012 (8-10) ft BGS	SB-2029 032912-EB-064 3/29/2012 (0-2) ft BGS	SB-2029 032912-EB-065 3/29/2012 (2-4) ft BGS	SB-2029 032912-EB-066 3/29/2012 (4-6) ft BGS	SB-2029 032912-EB-067 3/29/2012 (6-8) ft BGS	SB-2029 032912-EB-068 3/29/2012 (8-10) ft BGS	SB-2030 032912-EB-069 3/29/2012 (0-2) ft BGS	SB-2030 032912-EB-070 3/29/2012 (2-4) ft BGS	SB-2030 032912-EB-071 3/29/2012 (4-6) ft BGS
Polychlorinated Biphenyls (1	PCBs)										
Aroclor-1016 (PCB-1016)	mg/kg	0.48 U	2 U	0.028 U	0.14 U	0.44 U	0.0092 U	0.084 U	0.011	0.33 U	0.071 U
Aroclor-1221 (PCB-1221)	mg/kg	0.96 U	3.9 U	0.055 U	0.27 U	0.87 U	0.019 U	0.17 U	0.012	0.65 U	0.15 U
Aroclor-1232 (PCB-1232)	mg/kg	0.48 U	2 U	0.028 U	0.14 U	0.44 Ų	0.0092 U	0.084 U	0.02	0.33 U	0.071 U
Aroclor-1242 (PCB-1242)	mg/kg	17	36	0.028 U	0.14 U	0.44 U	0.0092 U	0.084 U	0.014	0.33 U	0.071 U
Aroclor-1248 (PCB-1248)	mg/kg	0.48 U	2 U	0.48	3.6	13	0.0092 U	0.084 U	0.054	11	0.7
Aroclor-1254 (PCB-1254)	mg/kg	0.48 U	2 U	0.028 U	0.14 U	0.44 U	0.0092 U	0.084 U	0.076	0.33 U	0.071 U
Aroclor-1260 (PCB-1260)	mg/kg	0.48 U	2 U	0.028 U	0.14 U	0.44 U	0.0092 U	0.084 U	0.0056 U	0.33 U	0.071 U
Total PCBs	mg/kg	17 ^{pq}	36 ^{pq}	0.48	3.6	13 ^p] ND	ND	0.076	11 ^p	0.7

Sample Location Sample Identification (SO-56) Sample Date Sample Depth Sample Type	394-) Units	SB-2030 032912-EB-072 3/29/2012 (6-8) ft BGS	SB-2030 032912-EB-073 3/29/2012 (8-10) ft BGS	MW-16 011210-CB-015 1/12/2010 (8-10) ft BGS	MW-16 011210-CB-016 1/12/2010 (3-5) ft BGS	MW-16 011210-CB-017 1/12/2010 (0-2) ft BGS
Polychlorinated Biphenyls (F	PCBs)					
Aroclor-1016 (PCB-1016)	mg/kg	0.49 U	0.35 U	0.012 U	0.07 U	0.79 UJ
Aroclor-1221 (PCB-1221)	mg/kg	0.98 U	0.69 U	0.012 U	0.07 U	0.79 UJ
Aroclor-1232 (PCB-1232)	mg/kg	0.49 U	0.35 U	0.012 U	0.07 U	0.79 UJ
Aroclor-1242 (PCB-1242)	mg/kg	14	0.35 U	0.012 U	0.07 U	0.79 UJ
Aroclor-1248 (PCB-1248)	mg/kg	0.49 U	9	0.012 U	0.78	8.1 J
Aroclor-1254 (PCB-1254)	mg/kg	0.49 U	0.35 U	0.012 U	0.24 J	2.9 J
Aroclor-1260 (PCB-1260)	mg/kg	0.49 U	0.35 U	0.012 U	0.089 J	0.79 UJ
Total PCBs	mg/kg	14 ^p	9 ^p	ND	1.109 J	11 J ^p

ATTACHMENT A STRATIGRAPHIC SOIL BORING LOGS



Page 1 of 1

PROJECT NAME: FORMER PLAINWELL, INC. MILL PROPERTY


PROJECT NUMBER: 056394

CLIENT: WEYERHAEUSER COMPANY

LOCATION: PLAINWELL, MI

HOLE DESIGNATION: SB-2016

DATE COMPLETED: March 29, 2012 DRILLING METHOD: DIRECT PUSH





Page 1 of 1

PROJECT NAME: FORMER PLAINWELL, INC. MILL PROPERTY

PROJECT NUMBER: 056394


CLIENT: WEYERHAEUSER COMPANY

LOCATION: PLAINWELL, MI

HOLE DESIGNATION: SB-2017

DATE COMPLETED: March 29, 2012

DRILLING METHOD: DIRECT PUSH





Page 1 of 1

PROJECT NAME: FORMER PLAINWELL, INC. MILL PROPERTY

PROJECT NUMBER: 056394

CLIENT: WEYERHAEUSER COMPANY

LOCATION: PLAINWELL, MI

HOLE DESIGNATION: SB-2018

DATE COMPLETED: March 29, 2012

DRILLING METHOD: DIRECT PUSH

DEPTH	STRATIGRAPHIC DESCRIPTION & REMARKS			BOREHOLE		SAMPLE					
ft BGS	NORTHING: 346895.77 GROUND S		ft BGS 724.7			NUMBER	INTERVAL	REC (%)	'N' VALUE	PID (ppm)	
	EASTING: 12778857.1	T. S. S.		VIIIIIIII		Ž	N N	Ŗ	ż	- B	
	SP-SAND, trace silt, trace coarse gravel, poorly graded, brown, moist TOPSOIL	<u> </u>	723.7 723.5			0.2				1.1	
-2 -4	SP-SAND, trace silt, trace coarse gravel, poorly graded, brown, moist - light brown from 2.0 to 2.5ft BGS - slag, black cinders, brick debris from 3.0 to 4.0ft BGS				— 2-1/4" BOREHOLE	1DP (2-4' -025)		30		0.4	
-6	- coarse gravel, reddish brown at 5.0ft BGS				Backfilled	46'		=		0.5	
-8	- coarse sand, moist at 7.5ft BGS				WITH BENTONITE CHIPS	6-8' -027 2DP		50		0.7	
						8-10° -028			:	1.1	
-10	END OF BOREHOLE @ 10.0ft BGS	111	714.7	WILLIAM I	•						
-12											
- 14											
-16											
- 1 <u>8</u>							12				
-20							1				
-22											
-24											
	A TABLES NO. 10 TO THE TABLES	NOT 5=			TIGHT : -: -						
	NOTES: MEASURING POINT ELEVATIONS MAY CHA	ANGE; RE	:FER TO C	UKRENT ELEVA	TION TABLE						
	CHEMICAL ANALYSIS										



Page 1 of 1

PROJECT NAME: FORMER PLAINWELL, INC. MILL PROPERTY

PROJECT NUMBER: 056394

CLIENT: WEYERHAEUSER COMPANY

LOCATION: PLAINWELL, MI

HOLE DESIGNATION: SB-2019

DATE COMPLETED: March 29, 2012

DRILLING METHOD: DIRECT PUSH

DEPTH ft BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. ft	BOREHOLE		SAMPLE					
πBGS	NORTHING: 346915.16 GROUND SURFACE EASTING: 12778852.89		BGS 725.4			NUMBER	INTERVAL	REC (%)	N' VALUE	PID (ppm)
	SP-SAND, trace fine and coarse gravel, fine					ž	Z	~	ż	2
	grained sand, poorly graded, brown					0-2° -014				98
∙2	TOPSOIL SP-SAND, trace fine and coarse gravel, fine		723.4 723.2		2-1/4"	1DP 2-4"		70		10
4	grained sand, poorly graded, brown - trace silt, dark brown at 3.0ft BGS				BOREHOLE	-015				10
	- coal fragments, wood debris at 4.5ft BGS CL-CLAY, trace fine sand, fine grained, poorly	11111	720.4			(4°,6)				35
6	graded, low plasticity, light brown, moist				— BACKFILLED WITH					
					BENTONITE CHIPS	8 77 2DP		50		3.1
·8	- wet at 8.5ft BGS		716.4			8-10° -018				2.9
10	SP-SAND, trace fine and coarse gravel, trace silt, coarse grained sand, brown, wet		715,4			₹				
	END OF BOREHOLE @ 10.0ft BGS					:			:	
12										
14										
· 16										
10										
18										
-20										
- 22										
								! !		
24										
	NOTES: MEASURING POINT ELEVATIONS MAY CHANGE	GE; RE	FER TO C	JRRENT ELEV	ATION TABLE				LI	-
	CHEMICAL ANALYSIS									



Page 1 of 1

PROJECT NAME: FORMER PLAINWELL, INC. MILL PROPERTY

PROJECT NUMBER: 056394


CLIENT: WEYERHAEUSER COMPANY

LOCATION: PLAINWELL, MI

HOLE DESIGNATION: SB-2020

DATE COMPLETED: March 29, 2012

DRILLING METHOD: DIRECT PUSH FIELD PERSONNEL: E. BATENBURG





Page 1 of 1

PROJECT NAME: FORMER PLAINWELL, INC. MILL PROPERTY

PROJECT NUMBER: 056394

CLIENT: WEYERHAEUSER COMPANY

LOCATION: PLAINWELL, MI

HOLE DESIGNATION: SB-2021

DATE COMPLETED: March 29, 2012

DRILLING METHOD: DIRECT PUSH

	STRATIGRAPHIC DESCRIPTION & REMARKS NORTHING: 346917.81 EASTING: 12778862.08 TOPSOIL SP-SAND, trace fine and coarse gravel, fine grained sand, poorly graded, light brown CL-CLAY, trace fine sand, trace silt, trace coarse gravel, poorly graded, low plasticity, gray, moist - black at 7.5ft BGS END OF BOREHOLE @ 10.0ft BGS	RFACE	ft BGS 724.7 724.6 719.8		— 2-1/4" BOREHOLE — BACKFILLED WITH BENTONITE CHIPS	0-2-4-505 0-2-4-505 1DP 2-4-505 (6-6-507) (8-10°8) (8-10°8)	INTERVAL	99 REC (%)	'N' VALUE	3.5 2.8 0.7
6	SP-SAND, trace fine and coarse gravel, fine grained sand, poorly graded, light brown CL-CLAY, trace fine sand, trace silt, trace coarse gravel, poorly graded, low plasticity, gray, moist - black at 7.5ft BGS		719.8		— BACKFILLED WITH	0-2 		60		3.5 2.8 0.7
12 14 16 18 20										
24	NOTES; MEASURING POINT ELEVATIONS MAY CHAN	 GE; RE	FER TO C	CURRENT ELEVA	ATION TABLE		ı			



Page 1 of 1

PROJECT NAME: FORMER PLAINWELL, INC. MILL PROPERTY

PROJECT NUMBER: 056394


CLIENT: WEYERHAEUSER COMPANY

LOCATION: PLAINWELL, MI

HOLE DESIGNATION: SB-2022

DATE COMPLETED: March 29, 2012

DRILLING METHOD: DIRECT PUSH





Page 1 of 1

PROJECT NAME: FORMER PLAINWELL, INC. MILL PROPERTY

PROJECT NUMBER: 056394


CLIENT: WEYERHAEUSER COMPANY

LOCATION: PLAINWELL, MI

HOLE DESIGNATION: SB-2023

DATE COMPLETED: March 29, 2012

DRILLING METHOD: DIRECT PUSH





Page 1 of 1

PROJECT NAME: FORMER PLAINWELL, INC. MILL PROPERTY

PROJECT NUMBER: 056394


CLIENT: WEYERHAEUSER COMPANY

LOCATION: PLAINWELL, MI

HOLE DESIGNATION: SB-2024

DATE COMPLETED: March 29, 2012

DRILLING METHOD: DIRECT PUSH FIELD PERSONNEL: E. BATENBURG





Page 1 of 1

PROJECT NAME: FORMER PLAINWELL, INC. MILL PROPERTY

PROJECT NUMBER: 056394


CLIENT: WEYERHAEUSER COMPANY

LOCATION: PLAINWELL, MI

HOLE DESIGNATION: SB-2025

DATE COMPLETED: March 29, 2012

DRILLING METHOD: DIRECT PUSH





Page 1 of 1

PROJECT NAME: FORMER PLAINWELL, INC. MILL PROPERTY

PROJECT NUMBER: 056394

CLIENT: WEYERHAEUSER COMPANY

LOCATION: PLAINWELL, MI

HOLE DESIGNATION: SB-2026

DATE COMPLETED: March 29, 2012 DRILLING METHOD: DIRECT PUSH

DEPTH	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV.	BOREHOLE	SAMPLE					
t BGS		BGS	BOKEHOLE	BER	\\	(%)	I.UE	(mdc	
	NORTHING: 346924.15 GROUND SURFACE EASTING: 12778849.71	E 725.6		NUMBER	INTERVAL	REC (%)	'N' VALUE	PID (ppm)	
2	SP-SAND, with fine gravel, fine grained sand, poorly graded, brown			0-2' -044				0.1	
1	- possible coal fragments at 2.5ft BGS SM-SILTY SAND, trace fine and coarse gravel,	721.6	2-1/4" BOREHOLE	1DP 2-4 -045		60		1.2	
	fine grained, poorly graded, dark brown SP-SAND, trace fine gravel, poorly graded, light brown, moist	720.6		46 -046				0.7	
6	iigitt brown, moist		BACKFILLED WITH BENTONITE CHIPS	6-8' -047 2DP		50		0.1	
8	- coarse sand, trace coarse gravel and silt,	715.6		8-10° -048				0.6	
10	brown, moist at 9.8ft BGS END OF BOREHOLE @ 10.0ft BGS	715.6							
12									
14									
16									
18					!				
20									
22									
24									
	NOTES: MEASURING POINT ELEVATIONS MAY CHANGE;	REFER TO C	URRENT ELEVATION TABLE						
	·								



Page 1 of 1

PROJECT NAME: FORMER PLAINWELL, INC. MILL PROPERTY

PROJECT NUMBER: 056394

CLIENT: WEYERHAEUSER COMPANY

LOCATION: PLAINWELL, MI

HOLE DESIGNATION: SB-2027

DATE COMPLETED: March 29, 2012

DRILLING METHOD: DIRECT PUSH

EPTH	STRATIGRAPHIC DESCRIPTION & REMARKS		ELEV.	BORE	BOREHOLE		SAMPLE			
t BGS	NORTHING: 346927 GROUND SI	URFACE	BGS 724.9			NUMBER	INTERVAL	REC (%)	'N' VALUE	PID (ppm)
	EASTING: 12778859.67					Ž	INTE	쀭	ž	윤
	SP-SAND, with fine gravel, trace roots, fine grained, poorly graded, brown, moist TOPSOIL, with roots	3.7	723.9			02 044				0.9
2	SP-SAND, with fine gravel, trace roots, fine	1, ,11	722.9							
	grained, poorly graded, brown, moist				— 2-1/4" BOREHOLE	1DP 2-4' -045		50		1.0
1	- silt, with sand at 4.5ft BGS					45				1.1
)	CL CLAV trace fine cond and fine around fine	7777	718.9		- BACKFILLED	4-6° -046				
	CL-CLAY, trace fine sand and fine gravel, fine grained, low plasticity, gray, moist				WITH BENTONITE CHIPS	6-8' -047 2DP		50		0.7
3	SP-SAND, with silt, trace coarse gravel, fine grained sand, poorly graded, brown, moist		716.9			8-10° -048				1.3
0	END OF BOREHOLE @ 10.0ft BGS		714.9			(
•										
2										
4				·						
•										
6										
8										
20										
22						i				
24										
- →										
		LOE DE			7.01.7.01.5					
	NOTES: MEASURING POINT ELEVATIONS MAY CHAI	NGE; RE	FER TO CL	JKKENT ELEVA	TION TABLE					



Page 1 of 1

PROJECT NAME: FORMER PLAINWELL, INC. MILL PROPERTY

PROJECT NUMBER: 056394


CLIENT: WEYERHAEUSER COMPANY

LOCATION: PLAINWELL, MI

HOLE DESIGNATION: SB-2028

DATE COMPLETED: March 29, 2012

DRILLING METHOD: DIRECT PUSH





Page 1 of 1

PROJECT NAME: FORMER PLAINWELL, INC. MILL PROPERTY

PROJECT NUMBER: 056394


CLIENT: WEYERHAEUSER COMPANY

LOCATION: PLAINWELL, MI

HOLE DESIGNATION: SB-2029

DATE COMPLETED: March 29, 2012

DRILLING METHOD: DIRECT PUSH





Page 1 of 1

PROJECT NAME: FORMER PLAINWELL, INC. MILL PROPERTY

PROJECT NUMBER: 056394


CLIENT: WEYERHAEUSER COMPANY

LOCATION: PLAINWELL, MI

HOLE DESIGNATION: SB-2030

DATE COMPLETED: March 29, 2012

DRILLING METHOD: DIRECT PUSH



ATTACHMENT B DATA VALIDATION MEMORANDUM



14496 Sheldon Road, Suite #200 Plymouth, Michigan 48170

Telephone: (734) 453-5123

Fax: (734) 453-5201

www.CRAworld.com

MEMORANDUM

To:

Greg Carli

REF. NO.:

56394

FROM:

Rawa Fleisher/Paul Wiseman/ah/8/Det

DATE:

May 18, 2012

RE:

Data Quality Assessment and Full Validation Phase II RI Addendum No. 1 – March, 2012

Former Plainwell, Inc. Mill Property - Plainwell, Michigan

The following details a quality assessment and validation of the analytical data resulting from the March 29, 2012, collection of 73 soil samples and nine (9) quality control samples from the Former Plainwell, Inc. Mill Property Site in Plainwell, Michigan. The sample summary detailing sample identification, sample location, quality control samples, and analytical parameters is presented in Table 1. Sample analysis was completed at ALS Environmental (formerly Columbia Analytical Services) in Kelso, Washington (ALS-K) in accordance with the methodologies presented in Table 2.

The quality control criteria used to assess the data were established by the methods and the quality assurance project plan (QAPP). Application of quality assurance criteria was consistent with following guidance documents:

 "USEPA Contract Laboratory Program National Functional Guidelines for Organic Data Review", EPA-540/R-99/008, October 1999;

These guidelines are collectively referred to as "NFGs" in this Memorandum.

Sample Quantitation

The laboratory reported detected concentrations of polychlorinated biphenyls (PCB) laboratory's report limit (RL) but above the laboratory's method detection limit (MDL). The laboratory flagged these sample concentrations with a "J". These concentrations should be qualified as estimated (J) values unless qualified otherwise in this memorandum.

Sample Preservation and Holding Times

Sample holding time periods and preservation requirements are presented in Table 2.

The samples were prepared and/or analyzed within the specified holding time periods.

The remaining samples were shipped and maintained in accordance with the sample preservation requirements.



Initial Calibration - Organic Analyses

Initial calibration data are used to demonstrate that each instrument is capable of generating acceptable quantitative data. A five point calibration curve containing all compounds of interest is analyzed to characterize instrument response for each over a specific concentration range.

Initial calibration criteria for organic analyses are evaluated against the following criteria:

i. GC (all compounds using an average for multi-response compounds) – the percent RSD must not exceed 20 percent or a correlation coefficient of 0.995 when linear regression calibration curves are used.

Calibration standards were analyzed at the required frequency and the results met the above criteria for linearity and sensitivity.

Continuing Calibration - Organic Analyses

To ensure that each instrument was capable of producing acceptable quantitative data over the analysis period, continuing calibration standards must be analyzed every 12 hours for GC/MS analyses and every 10 samples by GC. The following criteria are employed to evaluate the continuing calibration data:

- i. GC (all compounds using average for multi-response compounds) the percent difference between mean initial calibration factor and the continuing calibration factor must not exceed 15 percent; and
- ii. GC (compounds determined by linear regression) the percent drift between the true value and the continuing calibration value must not exceed 15 percent.

Calibration standards were analyzed at the required frequency and the results met the above criteria for instrument sensitivity and linearity of response and sensitivity.

Method Blank Samples

Method blank samples are prepared from a purified sample matrix and are processed concurrently with investigative samples to assess the presence and the magnitude of sample contamination introduced during sample analysis. Method blank samples are analyzed at a minimum frequency of one per analytical batch and target analytes should be non-detect.

The method blank samples did not contain target compounds with concentrations that impacted the investigative samples.

Surrogate Compounds - Organic Analyses

Individual sample performance for organic analyses was monitored by assessing the results of surrogate compound percent recoveries. Surrogate percent recoveries are reviewed against the laboratory developed control limits provided in the analytical report.

The PCB surrogate recoveries could not be measured or evaluated in several samples due to dilutions required to successfully analyze the samples. No qualification of these samples was required. The surrogate recovery acceptance criteria were met for all samples that could be.

Matrix Spike/Matrix Spike Duplicate Analyses

To assess the long term accuracy and precision of the analytical methods on various matrices, matrix spike/matrix spike duplicate (MS/MSD) percent recoveries and the relative percent difference (RPD) of the concentrations were determined. The organic MS/MSD percent recovery and RPD control limits are established by the laboratory. The inorganic control limits are defined by the methods or the laboratory and the NFG. The samples selected for MS/MSD analysis are identified in Table 1.

The samples that should be qualified due to violation of MS/MSD percent recovery criteria and/or RPD are outlined in Table 3. The MS/MSD percent recoveries could not be measured due in some samples to the dilutions required to successfully analyze the samples. No qualification was required. The MS/MSD percent recoveries and associated RPD acceptance criteria were met in the sample analyses that could be evaluated.

Laboratory Control Sample

The laboratory control sample (LCS) analyses serve as a monitor of the overall performance in all steps of the sample analysis and are analyzed with each sample batch. The LCS percent recoveries were evaluated against method and laboratory established control limits.

The LCS percent recoveries were within the laboratory control limits or did not warrant qualification, indicating that an acceptable level of overall performance was achieved.

Target Compound Identification

To minimize erroneous compound identification during organic analyses, qualitative criteria including compound retention time and mass spectra (if applicable) were evaluated according to identification criteria established by the methods. The sample(s) identified in Table 1 were reviewed. The organic compounds reported adhered to the specified identification criteria.

Target Compound Quantitation

The reported quantitation results and detection limits were checked to ensure results reported were accurate. The sample(s) identified in Table 1 were reviewed. No discrepancies were found between the raw data and the sample results reported by the laboratory.

Field Quality Assurance/Quality Control

The field quality assurance/quality control consisted of nine (9) field duplicate sample sets.

Field Duplicate Samples

Overall precision for the sampling event and laboratory procedures was monitored using the results of the field duplicate sample sets. The RPDs associated with these duplicate samples must be less than 100 percent. If the reported concentration in either the investigative sample or its duplicate is less than five times the RL, the evaluation criteria is two times the RL value.

Field Quality Assurance/Quality Control (Continued)

Table 4 presents the RPDs of detected analytes in duplicate sample sets with qualifiers. The data indicate that an adequate level of precision was achieved for the sampling event.

System Performance

System performance between various quality control checks was evaluated to monitor for changes that may have caused the degradation of data quality. No technical problems or chromatographic anomalies were observed which would require qualification of the data.

Overall Assessment

The data were found to exhibit acceptable levels of accuracy and precision, based on the provided information, and may be used with the qualifications noted.

ŋ

SAMPLE COLLECTION AND ANALYSIS SUMMARY PHASE II RI ADDENDUM NO. 1 - MARCH, 2012 FORMER PLAINWELL, INC. MILL PROPERTY PLAINWELL, MICHIGAN

Sample Identification	Location	Matrix	Initial Sample Depth (ft. bgs)	Final Sample Depth (ft. bgs)	QC Samples	Collection Date (mm/dd/yyyy)	Collection Time (hr:min)	Analysis/Parameters
CRA SDG No. 05-35C	CAS (ALS) No. K	1202887						
SO-56394-032912-EB-001	SB-2020	Lioa	4	6		3/29/2012	10:58:00 AM	TCL PCB
SO-56394-032912-EB-002	SB-2020	soil	6 .	8		3/29/2012	11:00:00 AM	TCL PCB
SO-56394-032912-EB-004	SB-2021	soil	0	2		3/29/2012	11:02:00 AM	TCL PCB
SO-56394-032912-EB-004A	SB-2021	soil	0	2	FD (-004)	3/29/2012	11:02:00 AM	TCL PCB
SO-56394-032912-EB-005	SB-2021	soil	2	4		3/29/2012	11:20:00 AM	TCL PCB
SO-56394-032912-EB-006	SB-2021	soil	4	6		3/29/2012	11:21:00 AM	TCL PCB
SO-56394-032912-EB-009	SB-2016	soil	0	2		3/29/2012	11:41:00 AM	TCL PCB
SO-56394-032912-EB-010	SB-2016	soil	2	4		3/29/2012	11:42:00 AM	TCL PCB
SO-56394-032912-EB-011	SB-2016	soil	4	6		3/29/2012	11:43:00 AM	TCL PCB
SO-56394-032912-EB-014	SB-2019	soil	0	2		3/29/2012	11:58:00 AM	TCL PCB
SO-56394-032912-EB-015	SB-2019	soil	2	4		3/29/2012	11:59:00 AM	TCL PCB
SO-56394-032912-EB-016	SB-2019	soil	4	6	MS/MSD	3/29/2012	12:00:00 PM	TCL PCB
SO-56394-032912-EB-019	SB-2024	soil	0	2		3/29/2012	12:41:00 PM	TCL PCB
SO-56394-032912-EB-019A	SB-2024	soil	0	2	FD (-019)	3/29/2012	12:41:00 PM	TCL PCB
SO-56394-032912-EB-020	SB-2024	soil	2	4		3/29/2012	12:43:00 PM	TCL PCB
SO-56394-032912-EB-021	SB-2024	soil	4	6		3/29/2012	12:45:00 PM	TCL PCB
SO-56394-032912-EB-024	SB-2018	soil	0	2		3/29/2012	1:00:00 PM	TCL PCB
SO-56394-032912-EB-025	SB-2018	soil	2	4		3/29/2012	1:00:00 PM	TCL PCB
SO-56394-032912-EB-026	SB-2018	soil	4	6		3/29/2012	1:11:00 PM	TCL PCB
SO-56394-032912-EB-029	SB-2023	soil	0	2		3/29/2012	1:12:00 PM	TCL PCB
SO-56394-032912-EB-029A	SB-2023	soil	. 0	2 .	FU (-029), MS/MSU	3/29/2012	1:12:00 PM	TCL PCB
SO-56394-032912-EB-030	SB-2023	soil	2	4		3/29/2012	1:41:00 PM	TCĻ PCB
SO-56394-032912-EB-030A	. SB-2023	soil	2	4	FD (-030)	3/29/2012	1:41:00 PM	TCL PCB
SO-56394-032912-EB-031	SB-2023	soil	4	6		3/29/2012	1:42:00 PM	TCL PCB
SO-56394-032912-EB-034	SB-2017	soil	0	2		3/29/2012	1:44:00 PM	TCL PCB
SO-56394-032912-EB-035	SB-2017	soil	2	4		3/29/2012	1:45:00 PM	TCL PCB
SO-56394-032912-EB-036	SB-2017	soil	4	6		3/29/2012	1:46:00 PM	TCL PCB
SO-56394-032912-EB-039	SB-2022	soil	0	2	MS/MSD	3/29/2012	1:52:00 PM	TCL PCB
SO-56394-032912-EB-040	SB-2022	soil	2	4	•	3/29/2012	1:53:00 PM	TCL PCB
SO-56394-032912-EB-041	SB-2022	soil	4	6		3/29/2012	1:54:00 PM	TCL PCB
CRA SDG No. 05-36C	CAS (ALS) No. KI	202934						
SO-56394-032912-EB-003	SB-2020	soil	8	10		3/29/2012	11:02:00 AM	TCL PCB
SO-56394-032912-EB-007	SB-2021	soil	6	8		3/29/2012	11:22:00 AM	TCL PCB
SO-56394-032912-EB-008	SB-2021	soil	8	10		3/29/2012	11:24:00 AM	TCL PCB
SO-56394-032912-EB-012	SB-2016	soil	6	8		3/29/2012	11:44:00 AM	TCL PCB
SO-56394-032912-EB-013	SB-2016	sofl	8	10		3/29/2012	11:45:00 AM	TCL.PCB

TABLE 1

SAMPLE COLLECTION AND ANALYSIS SUMMARY PHASE II RI ADDENDUM NO. 1 - MARCH, 2012 FORMER PLAINWELL, INC. MILL PROPERTY PLAINWELL, MICHIGAN

Sample Identification	Location	Matrix	Initial Sample Depth (ft. bgs)	Final Sample Depth (ft. bgs)	QC Samples	Collection Date (mn/dd/yyyy)	Collection Time (hr:min)	Analysis/Parameters
CRA SDG No. 05-36C	CAS (ALS) No. K	1202934						
SO-56394-032912-EB-017	SB-2019	soil	6 .	8		3/29/2012	12:01:00 PM	TCL PCB
SO-56394-032912-EB-018	SB-2019	soil	8	10		3/29/2012	12:02:00 PM	TCL PCB
SO-56394-032912-EB-022	\$B-2024	soil	6	8		3/29/2012	12:47:00 PM	TCL PCB
SO-56394-032912-EB-023	SB-2024	soil	8	10		3/29/2012	12:48:00 PM	TCL PCB
SO-56394-032912-EB-027	SB-2018	soil	6	8		3/29/2012	1:11:00 PM	TCL PCB
SO-56394-032912-EB-028	SB-2018	soil	8	10		3/29/2012	1:12:00 PM	TCL PCB
SO-56394-032912-EB-032	\$B-2023	soil	6	8		3/29/2012	1:43:00 PM	TCL PCB
SO-56394-032912-EB-033	SB-2023	soil	8	10		3/29/2012	1:44:00 PM	TCL PCB
SO-56394-032912-EB-037	SB-2017	soil	6	8		3/29/2012	1:47:00 PM	TCL PCB
SO-56394-032912-EB-037Λ	SB-2017	soil	6	8	FD (-037)	3/29/2012	1:47:00 PM	TCL PCB
SO-56394-032912-EB-038	SB-2017	soil	8	10		3/29/2012	1:48:00 PM	TCL PCB
SO-56394-032912-EB-038A	SB-2017	soil	8	10	FD (-038), MS/MSD	3/29/2012	1:48:00 PM	TCL PCB
SO-56394-032912-EB-042	SB-2022	soil	6	8		3/29/2012	1:55:00 PM	TCL PCB
SO-56394-032912-EB-043	SB-2022	soil	8	10		3/29/2012	1:56:00 PM	TCL PCB
SO-56394-032912-EB-043A	SB-2022	soil	8	10	FD (-043)	3/29/2012	1:56:00 PM	TCL PCB
SO-56394-032912-EB-044	\$8-2026	soil	0	2	MS/MSD	3/29/2012	2:50:00 PM	TCL PCB
SO-56394-032912-EB-045	SB-2026	soil	. 2	. 4		3/29/2012	2:51:00 PM	TCL PCB
SO-56394-032912-EB-045A	58-2026	soil	2	4	FD (-045)	3/29/2012	2:51:00 PM	TCL PCB
SO-56394-032912-EB-046	SB-2026	soil	4	6		3/29/2012	2:52:00 PM	TCL PCB
SO-56394-032912-EB-047	SB-2026	soil	6	8	•	3/29/2012	2:53:00 PM	TCL PCB
SO-56394-032912-EB-048	SB-2026	soil	8	10		3/29/2012	2:54:00 PM	TCL PCB
SO-56394-032912-EB-049	SB-2027	soil	0	2		3/29/2012	3:05:00 PM	TCL PCB
SO-56394-032912-EB-050	SB-2027	soil	2	4	MS/MSD	3/29/2012	3:06:00 PM	TCL PCB
SO-56394-032912-EB-051	SB-2027	soil	4	6		3/29/2012	3:07:00 PM	TCL PCB
SO-56394-032912-EB-052	SB-2027	soil	6	8		3/29/2012	3:08:00 PM	TCL PCB
SO-56394-032912-EB-052A	SB-2027	soil	6	8	FD (-052)	3/29/2012	3:08:00 PM	TCL PCB
SO-56394-032912-EB-053	SB-2027	soil	8	10		3/29/2012	3:09:00 PM	TCL PCB
SO-56394-032912-EB-054	SB-2028	soil	0	2		3/29/2012	3:11:00 PM	TCL PCB
SO-56394-032912-EB-055	SB-2028	soil	2	4		3/29/2012	3:12:00 PM	TCL PCB
SO-56394-032912-EB-056	SB-2028	soil	4	6		3/29/2012	3:13:00 PM	TCL PCB
SO-56394-032912-EB-057	SB-2028	soil	6	8		3/29/2012	3:14:00 PM	TCL PCB
SO-56394-032912-EB-058	SB-2028	soil	8	10		3/29/2012	3:15:00 PM	TCL PCB
SO-56394-032912-EB-059	SB-2025	soil	0	2		3/29/2012	3:30:00 PM	TCL PCB
SO-56394-032912-EB-060	SB-2025	soil	2	4		3/29/2012	3:31:00 PM	TCL PCB
SO-56394-032912-EB-061	SB-2025	soil	4	6		3/29/2012	3:32:00 PM	TCL PCB
SO-56394-032912-EB-062	SB-2025	soil	6	8		3/29/2012	3:33:00 PM	TCL PCB
SO-56394-032912-EB-063	SB-2025	soil	8	10		3/29/2012	3:34:00 PM	TCL PCB
SO-56394-032912-EB-064	SB-2029	soil	0	2		3/29/2012	3:40:00 PM	TCL PCB

SAMPLE COLLECTION AND ANALYSIS SUMMARY PHASE II RI ADDENDUM NO. 1 - MARCH, 2012 FORMER PLAINWELL, INC. MILL PROPERTY PLAINWELL, MICHIGAN

Sample Identification	Location	<i>Matri</i> x	Initial Sample Depth (ft. bgs)	Final Sample Depth (ft. bgs)	QC Samples	Collection Date (mm/dd/yyyy)	Collection Time (hr:min)	Analysis/Parameters	
CRA SDG No. 05-36C	CAS (ALS) No. K	1202934							
SO-56394-032912-EB-065	SB-2029	soil	2	4		3/29/2012	3:41:00 PM	TCL PCB	
SO-56394-032912-EB-066	SB-2029	soil	4	6		3/29/2012	3:42:00 PM	TCL PCB	
SO-56394-032912-EB-067	SB-2029	soil	6	8		3/29/2012	3:43:00 PM	TCL PCB	
SO-56394-032912-EB-068	SB-2029	soil	8	10		3/29/2012	3:44:00 PM	TCL PCB	
SO-56394-032912-EB-069	SB-2030	soil	0	2		3/29/2012	4:10:00 PM	TCL PCB	
SO-56394-032912-EB-070	SB-2030	soil	2	4		3/29/2012	4:11:00 PM	TCL PCB	
SO-56394-032912-EB-071	SB-2030	soil	4	6		3/29/2012	4:12:00 PM	TCL PCB	
SO-56394-032912-EB-072	SB-2030	soil	6	8		3/29/2012	4:13:00 PM	TCL PCB	
SO-56394-032912-EB-073	SB-2030	soil	8	10		3/29/2012	4:14:00 PM	TCL PCB	

Notes:

FD - Field Duplicate Sample of sample in parenthesis

MS/MSD - Matrix Spike/Matrix Spike Duplicate

PCB - Polychlorinated biphenyls QC - Quality Control

TCL - Target Compound List

TABLE 2

12

SUMMARY OF ANALYTICAL METHODS, HOLDING TIME PERIODS, AND PRESERVATIVES PHASE II RI ADDENDUM NO. 1 - MARCH, 2012 FORMER PLAINWELL, INC. MILL PROPERTY PLAINWELL, MICHIGAN

Parameter	Method 1	Matrix	Holding Time	Preservation ²
PCB .	SW-846 8082	Soil	- 14 days from sample collection to extraction - 40 days from extraction to completion of analysis	Iced, $4 \pm 2^{\circ}$ C

Notes

SW-846 - "Test Methods for Evaluating Solid Waste, Physical/Chemical Methods", SW-846, 3rd Edition, and Promulgated updates, November 1986

PCB - Polychlorinated biphenyls

² pH preservativation is not required in soil samples.

¹ Method References:

TABLE 3

SUMMARY OF QUALIFIED SAMPLE DATA DUE TO OUTLYING MATRIX SPIKE/MATRIX SPIKE DUPLICATE RECOVERIES AND/OR RELATIVE PERCENT DIFFERENCE PHASE II RI ADDENDUM NO. 1 - MARCH, 2012 FORMER PLAINWELL, INC. MILL PROPERTY PLAINWELL, MICHIGAN

		MS	MSD		Control	Limits	Associated	Qualified	
Parameter	Analyte	%Rec	%Rec	RPD	%Rec	RPD	Sample ID	Result	Units
									,,
PCB	Aroclor-1248	265	185	36	27-128	40	SO-56394-032912-EB-029A	380 J	μg/kg
PCB	Aroclor-1242	334	403	19	27-128	40	SO-56394-032912-EB-038A	63 J	μg/kg
PCB	Aroclor-1248	166	130	25	27-128	4 0	SO-56394-032912-EB-050	92 J	μg/kg

Notes:

J - Estimated Concentration

MS - Matrix Spike

MSD - Matrix Spike Duplicate

RPD - Relative Percent Difference

%Rec - Percent Recovery

PCB - Polychlorinated biphenyls

TABLE 4

SUMMARY OF QUALIFIED SAMPLE DATA DUE TO VARIABILITY IN FIELD DUPLICATE RESULTS PHASE II RI ADDENDUM NO. 1 - MARCH, 2012 FORMER PLAINWELL, INC. MILL PROPERTY PLAINWELL, MICHIGAN

Parameter	Analyte	Criteria	RPD/ Diff	Sample ID	Qualified Result	Field Duplicate Sample ID	Qualified Result	Units
PCB	Aroclor-1254	RPD	170	SO-56394-032912-EB-004	6.9 UJ	SO-56394-032912-EB-004A	<i>7</i> 2 J	mg/kg
PCB	Aroclor-1242	RPD	130	SO-56394-032912-EB-043	16000 J	SO-56394-032912-EB-043A	3300 J	mg/kg
PCB	Aroclor-1248	RPD	110	SO-56394-032912-EB-019	7.2 UJ	SO-56394-032912-EB-019A	24 J	mg/kg

Notes:

RPD - Relative Percent Difference

Diff - Difference

PCB - Polychlorinated biphenyls

J - Estimated Concentration

ATTACHMENT C LABORATORY ANALYTICAL DATA